

EBHS FOOD SERVICE EQUIPMENT – REQUEST FOR PROPOSAL

ADDENDUM NO. 1

MAY 6<sup>th</sup>, 2016

BID DATE: Friday May 20<sup>th</sup> 2016 11:00 a.m. (CDT)

***The following additions, deletions, modifications, or clarifications shall be made to the appropriate sections of the plans and specifications and shall become a part of the Contract Documents. Bidders shall acknowledge receipt of this Addendum on the Bid form.***

A1-1 Addendum 1, PART 5 - ITEM SPECIFICATIONS, Item # 6

A. ADDITION: The East Buchanan C-1 school district is seeking a Turn-Key installation for Item # 6 – Condensate Hood. Bid pricing for Item # 6 shall include all related costs for labor, material, ductwork, and anything else which is required for a complete installation resulting in a fully functional condensate hood, excluding normal roof patching from the mounting of the exhaust fan curb on the roof, electrical rough-in, and final electrical connections. The roofing contractor will be responsible for patching around the one (1) roof penetration incurred during normal installation. The electrical contractor will be responsible for final electrical connections.

A1-2 Addendum 1, PART 5 - ITEM SPECIFICATIONS, Item # 13

A. ADDITION: The East Buchanan C-1 school district is seeking a Turn-Key installation for Item # 13 – Exhaust Hood. Bid pricing for Item # 13 shall include all related costs for labor, material, ductwork, and anything else which is required for a complete installation resulting in a fully functional exhaust hood and make-up air unit, excluding normal roof patching from the mounting of the exhaust fan and make-up air curbs on the roof, the plumbing of natural gas line for the tempered make-up air unit, electrical rough-in, and final electrical connections. The roofing contractor will be responsible for patching around the two (2) roof penetrations incurred during normal installation. The plumbing contractor will be responsible for running the gas line to the required location during normal installation. The electrical contractor will be responsible for final electrical connections.

END OF ADDENDUM NO. 1